

**ADDITIONS AND RENOVATIONS TO  
02060  
PENFIELD UNITED METHODIST CHURCH**

**SECTION  
REMOVALS**

PART 1 - GENERAL

1.01 RELATED DOCUMENTS

- .1 Drawings and general provisions of Contract, including General and Supplemental Conditions and Divisions -1 Specification sections, apply to work of this section.
- .2 Refer to Section 01010–Summary of work for specific contractor responsibility for demolition.

1.02 DESCRIPTION OF WORK

- .1 The extent of removals is shown on drawings or if not indicated on drawings, provide extent of removals as implicitly required to comply with project requirements. Each Sub-Contractor shall be responsible for doing removals related to the nature of his sub-Contract.
- .2 Owner assumes no responsibility for actual condition of structures to be removed.
- .3 Conduct removal operation and removal of debris to ensure minimum interference with roads. Streets. Parking lot, walks, and other adjacent occupied or used facilities.
- .4 Do not close or obstruct streets walks or other occupied or used facilities without permission from authorities having jurisdiction. Provide alternate routes around closed or obstructed traffic ways if required by governing regulations.
- .5 Ensure safe passage of persons around area of removals. Conduct operation to prevent injury to adjacent buildings, structures, other facilities and persons.
- .6 Promptly repair damages caused to adjacent facilities by removal operation at no cost to Owner.
- .7 Maintain existing utilities indicated to remain, keep in service, and protect against damage during removal operations.
- .8 If materials are encountered that are suspected to be friable asbestos-containing materials, immediately stop work and exit the area. Seal the area off so no persons may enter and post signs notifying all personnel that are not allowed to enter the area. Notify the Owner of the location of the suspect material after discovery.
- .9 The Contractor shall protect the path of travel used to bring materials in the building.

PART 2 – PRODUCTS (not applicable)

PART 3 - EXECUTION

3.01 REMOVALS

**ADDITIONS AND RENOVATIONS TO  
02060**

**SECTION**

**PENFIELD UNITED METHODIST CHURCH**

**REMOVALS**

- .1 Clean adjacent structures and improvements of dust, dirt and debris caused by removal operations, as directed by architect or governing authorities.

3.02 DISPOSAL OF REMOVED MATERAILS

- .1 Remove from site, debris, rubbish, and other materials resulting from removal operations.

END OF SECTION 02060